

		SCHEDULE OF RATES - AFTER SALSSE SERVICES WITH ALL ASSOCIATED WORKS					Tender NO.: SGL:TEND:36:2022-23	
		LOCATION : MEHSANA, UNJHA AND ADJOINING AREA						
Item No.	Item Description	Unit	Total qty	Base Rate				
				Unit Rate in Rs	Applicable GST in %	Unit Rate in Rs incl. GST	Total Price in Rs. incl. GST	
A	B	C	D	E	F	G = E + (E X F)	H =D X G	
PART-D	AFTER SALSSE SERVICES (Document no.: P.019028 D 11077 019, P.019028 D 11077 020)		0.00					
D.1	Inst, Test, Com of 20 mm OD MDPE Pipe Open cut or Molling Labour	Mtr	918.00	132	18%	155.76	142987.68	
D.2	Supply of 20 mm OD PE pipe x SDR 9 (3.0 mm)	Mtr	918.00	29	18%	34.22	31413.96	
D.3	Alteration + Modification extra point row house		0.00					
D.3.1	Supply of Materials of additional points (kitchen point or Geyser point) in individual row house on per meter basis including fixing of 1/2" GI pipe, GI fittings viz. Elbow, Tee, Coupling, Nipple, powder coated clamp, Drilling of Hole (in RCC/Brick & Others) ,Gas tap and rubber tube etc. (Only Supply of Gas tap and rubber tube shall be paid as per unit rates mentioned in SOR. Rest All inclusive of rates) -Material only	Mtr	5508.00	202	18%	238.36	1312886.88	
D.3.2	Installation & comissioning of additional points (kitchen point or Geyser point) in individual row house on per meter basis including fixing of 1/2" GI pipe, GI fittings viz. Elbow, Tee, Coupling, Nipple, powder coated clamp, Drilling of Hole (in RCC/Brick & Others) ,Gas tap and rubber tube etc. (Only Supply of Gas tap and rubber tube shall be paid as per unit rates mentioned in SOR. Rest All inclusive of rates)- Service only	Mtr	5508.00	120	18%	141.60	779932.80	
D.4	Supply of 1/2" GI Pipe	Mtr	3162.00	150	18%	177.00	559674.00	
D.5	ITC -1/2" GI Pipe Row House		0.00			0.00	0.00	
D.5.1	Installation and Fixing of new 1/2" GI Pipe for alteration / Modification or shifting including fixing of GI Elbow , Coupling, Tee, Nipple, Union, Reducer, clamp etc for individual Row House, Bungalows - labor Rate	Mtr	3060.00	90	18%	106.20	324972.00	
D.6	ITC-1/2" GI Pipe High Rise Building		0.00					
D.6.1	Installation and Fixing of new 1/2" GI Pipe for alteration / Modification or shifting including fixing of GI Elbow , Coupling, Tee, Nipple, Union, Reducer, clamp etc for High rise Building using PETZEL- labour rates.	Mtr	102.00	70	18%	82.60	8425.20	
D.7	PDC Domestic row house		0.00					
D.7.1	Permanent Disconnection of domestic connection in individual row house including dismantling of 1/2 GI pipe, GI fittings, regulator, meter, Ball & appliance valve , Providing of 20 mm PE end cap in PE pipe out side customer premises with electrofusion welding process and return of materials to SGL specified stores with meter and regulator.	NOS	459.00	450	18%	531.00	243729.00	
D.8	PDC Domestic High Rise building		0.00					
D.8.1	Permanent Disconnection of domestic connection in High Rise Building (With or Without PETZEL) including dismantling of 1/2 GI pipe, GI fittings, regulator, meter, Ball & appliance valve , Providing end plug in GI riser outside customer premises and return of materials to SGL specified stores with meter and regulator.	NOS	26.00	120	18%	141.60	3681.60	
D.9	FDC Domestic row house		0.00					
D.9.1	Force Disconnection of Domestic Customer without PETZEL for each house including Removal of Meter and providing end plug. Rates include transportation of Meter	NOS	2716.00	210	18%	247.80	673024.80	
D.10	FDC Domestic High Rise Building		0.00					
D.10.1	Force Disconnection of Domestic Customer using PETZEL for each house including Removal of Meter and providing end plug. Rates include Transportation of Meter	NOS	136.00	85	18%	100.30	13640.80	
D10.2	Re connection of Force Disconnected Domestic Customer for each house including Re fitting Meter (Rates inclusive of transportation of Meter)	NOS	429.00	82	18%	96.76	41510.04	
D.11	Dismantling of 1/2" GI Pipe & Fittings in Individual Row House/Bungalows	MTR	2142.00	53	18%	62.54	133960.68	
D.12	Dismantling of 1/2" GI Riser & Fittings-	MTR	25.00	42	18%	49.56	1239.00	
D.13	Re Fitting of 1/2" GI Pipe for including fixing of GI Elbow , Coupling, Tee, Nipple, Union, Reducer, clamp etc	MTR	2142.00	155	18%	182.90	391771.80	
D.14	Supply of RCC guard with Painting & Stencilling -Material	NOS	510.00	157	18%	185.26	94482.60	
D.15	Installation of RCC guard with Painting & Stencilling -Labor	NOS	510.00	31	18%	36.58	18655.80	
D.16	Supply of Meter adaptor for Domestic Meter with O Ring - Material	NOS	2448.00	275	18%	324.50	794376.00	

		SCHEDULE OF RATES - AFTER SALSSE SERVICES WITH ALL ASSOCIATED WORKS					Tender NO.: SGL:TEND:36:2022-23	
		LOCATION : MEHSANA, UNJHA AND ADJOINING AREA						
Item No.	Item Description	Unit	Total qty	Base Rate				
				Unit Rate in Rs	Applicable GST in %	Unit Rate in Rs incl. GST	Total Price in Rs. incl. GST	
A	B	C	D	E	F	G = E + (E X F)	H =D X G	
D.17	Installation of Brass Meter adaptor for Domestic Meter with O Ring -Labor	NOS	2448.00	42	18%	49.56	121322.88	
D.18	Supply of Transition Fitting 1/2" -Material	NOS	510.00	160	18%	188.80	96288.00	
D.19	Installation & Testing of Transition Fitting 1/2" -Labor	NOS	510.00	42	18%	49.56	25275.60	
D.20	Installation & Testing of Gas Tap (1/2"- 6 mm)-Supply as SGL free issued Material	NOS	765.00	43	18%	50.74	38816.10	
D.21	Installation & Testing of Ball Valve,MCV/IV-1/2"-Supply as SGL Free issued Material	NOS	510.00	43	18%	50.74	25877.40	
D.22	AMC of PNG Domestic Connection>5 years-Material	NOS	25500.00	90	18%	106.20	2708100.00	
D.23	AMC of PNG Domestic Connection>5 years - Labor	NOS	25500.00	75	18%	88.50	2256750.00	
D.24	AMC of PNG Domestic Connection<5 years -Material	NOS	16320.00	78	18%	92.04	1502092.80	
D.25	AMC of PNG Domestic Connection<5 years - Labor	NOS	16320.00	65	18%	76.70	1251744.00	
D.26	AMC of Riser Upto G+5 floors -Once a Year Using PETZL -Material	NOS	51.00	160	18%	188.80	9628.80	
D.27	AMC of Riser Upto G+5 floors-Once a Year Using PETZL -Labor	NOS	51.00	105	18%	123.90	6318.90	
D.28	AMC of Riser each floor above 5th Floor-Once a year using PETZL - Material	NOS	26.00	160	18%	188.80	4908.80	
D.29	AMC of Riser each floor above 5th Floor -Once a year using PETZL - Labor	NOS	26.00	110	18%	129.80	3374.80	
D.30	Drilling of Hole in Brick wall / plastering	NOS	306.00	33	18%	38.94	11915.64	
D.31	Drilling of Hole in RCC	NOS	51.00	360	18%	424.80	21664.80	
D.32	Drilling of Hole in Others (Tile, Marble, Stone, Wood, Design, Granite, etc.)	NOS	26.00	360	18%	424.80	11044.80	
D.33	Supply of PVC Sleeve on GI Pipe with Insulation- Material	MTR	306.00	20	18%	23.60	7221.60	
D.34	Installation and Fixing of PVC Sleeve on GI Pipe with Insulation - Labor	MTR	306.00	10	18%	11.80	3610.80	
D.35	NG Conversion charges for 2 burner	NOS	700.00	52	18%	61.36	42952.00	
D.36	NG Conversion charges up to 4 burner	NOS	77.00	85	18%	100.30	7723.10	
D.37	NG Conversion charges for Oven / Hot plate or any others	NOS	26.00	85	18%	100.30	2607.80	
D.38	Installation of Rubber Hose (1 mtrs length as per IS 9573, Type II, Suraksha Mark)-SGL Free Issued Suresh Rubber Hose	NOS	790.00	42	18%	49.56	39152.40	
D.39	Supply & Installation of Reducer 32 X 20 mm	NOS	15.00	95	18%	112.10	1681.50	
D.40	Supply & Installation of Coupler 32 mm	NOS	15.00	62	18%	73.16	1097.40	
D.41	Supply & Installation of Coupler 20 mm	NOS	785.00	55	18%	64.90	50946.50	
D.42	Supply & Installation of Equal Tee 32 mm	NOS	15.00	170	18%	200.60	3009.00	
D.43	Supply & Installation of Equal Tee 20 mm	NOS	25.00	135	18%	159.30	3982.50	
D.44	Supply & Installation of End Cap 32 mm	NOS	25.00	110	18%	129.80	3245.00	
D.45	Supply & Installation of End Cap 20 mm	NOS	285.00	105	18%	123.90	35311.50	
D.46	Supply & Installation of Saddle 32 x 20 mm	NOS	15.00	320	18%	377.60	5664.00	
D.47	Supply, Installation and Fixing GI Fittings of 1/2" Elbow	NOS	1836.00	27	18%	31.86	58494.96	
D.48	Supply, Installation and Fixing GI Fittings of 1/2" Hex Nipple	NOS	5.00	27	18%	31.86	159.30	
D.49	Supply, Installation and Fixing GI Fittings of 1/2" NB Barrel Nipple	NOS	1224.00	27	18%	31.86	38996.64	
D.50	Supply, Installation and Fixing GI Fittings of 1/2" Coupling	NOS	612.00	27	18%	31.86	19498.32	
D.51	Supply, Installation and Fixing GI Fittings of 1/2" End Plug	NOS	1426.00	27	18%	31.86	45432.36	
D.52	Supply, Installation and Fixing GI Fittings of 1/2" hex Plug	NOS	15.00	27	18%	31.86	477.90	
D.53	Supply, Installation and Fixing GI fittings 1/2" Union	NOS	15.00	62	18%	73.16	1097.40	
D.54	Supply, Installation and Fixing GI Fittings of 1 " x 1/2" Reducer	NOS	15.00	68	18%	80.24	1203.60	
D.55	Supply, Installation and Fixing GI Fittings of 1 " x 1/2" Tee	NOS	15.00	72	18%	84.96	1274.40	
D.56	Supply, Installation and Fixing GI Fittings of 1/2" Tee	NOS	51.00	35	18%	41.30	2106.30	
D.57	Supply& Installation of 3/4" x 1/2" Bush	NOS	15.00	75	18%	88.50	1327.50	
D.58	Supply& Installation of 3/4" x 1" Bush	NOS	15.00	92	18%	108.56	1628.40	
D.59	Supply & Installation of Blind Meter Adaptor- GI (Temporary Disconnection of Dom. Customers)	NOS	1020.00	110	18%	129.80	132396.00	
D.60	Supply & Installation of domestic Regulator Inlet adaptor-Brass	NOS	51.00	155	18%	182.90	9327.90	

SCHEDULE OF RATES - AFTER SALS SERVICES WITH ALL ASSOCIATED WORKS		Tender NO.: SGL:TEND:36:2022-23
LOCATION : MEHSANA, UNJHA AND ADJOINING AREA		

Item No.	Item Description	Unit	Total qty	Base Rate			
				Unit Rate in Rs	Applicable GST in %	Unit Rate in Rs incl. GST	Total Price in Rs. incl. GST
A	B	C	D	E	F	G = E + (E X F)	H =D X G
D.61	Supply & Installation of domestic Regulator outlet adaptor-Brass	NOS	51.00	155	18%	182.90	9327.90
D.62	Supply & Installation of 1/2" GI Powder Coated Clamp with screw	NOS	2448.00	16	18%	18.88	46218.24
D.63	Supply & Installation of Rubber Tube Clamp	NOS	1581.00	8	18%	9.44	14924.64
D.64	Supply & Installation of Burner Jet (110 mm)	NOS	765.00	7	18%	8.26	6318.90
D.65	Supply & Installation of Burner Jet (125 mm)	NOS	918.00	7	18%	8.26	7582.68
D.66	Supply & Installation of " O " Ring for domestic meter / regulator	NOS	2448.00	5	18%	5.90	14443.20
D.67	Supply & Installation of 1/2" Union O Ring or Seal	NOS	8.00	5	18%	5.90	47.20
D.68	Supply & Installation of Warning Tape / Anti- Rodent Tape as per Owner Specification	MTR	918.00	16	18%	18.88	17331.84
D.69	Temporary Disconnection of PNG Domestic Customer with leak test of entire installation	NOS	1020.00	110	18%	129.80	132396.00
D.70	Reconnection of PNG Domestic Customer of PNG Domestic Customer with leak test of entire installation	NOS	2448.00	110	18%	129.80	317750.40
D.71	PNG Domestic Meter Check Survey (as per list provided by EIC) Includes - To check meter running status - Entire Leak test of the installation - Check for Meter tampering/Meter Slow/Meter Fast/Meter Stop - All supply items shall be paid as per unit rates mentioned in SOR. - No seperate rates shall be paid for House Lock Cases	NOS	4896.00	60	18%	70.80	346636.80
D.72	Replacement of Domestic Meters Includes - Issue of New Meter and replacing it with the old meter (due to Meter Stop, Meter Slow or Fast, Meter Tampering, Display Not proper, Leakake from Meter Body). - Leak Test of entire installation - Issue and returning the meters to the SGL Stores - All supply items shall be paid as per unit rates mentioned in SOR. - No Seperate rates shall be paid for House Lock/survey cases	NOS	489.60	135	18%	159.30	77993.28
TOTAL AMOUNT IN Rs. INCLUSIVE OF GST							15,178,085.12

- NOTE:**
- All SOR item shall be strictly quoted on E-tendering portal sgl.nprocure.com by the bidder in the price part of the bid, else will be rejected.
 - The SOR items would be operatable as per job requirement and quantities may vary on ± sides.
 - The general activities related to laying of PE pipe, installation of GI Pipe for domestic connection or customers as defined in tender document.
 - The scope as mentioned in the above SOR is of indicative nature only and shall include all activities as detailed in the relevant clauses of the tender document.
 - Bidder shall note that the quantities mentioned against each activity in Schedule of Rates are tentative only. These quantities subject to change based on actual requirement. Quantities in SOR for PNG connection is considered based on targets set by PNGRB. However, actual no. of execution may vary based on actual registrations received during the course of the contract period.
 - The quantites of individual item can varied as per site requirement. The payment will be made as per actual certified measurement at site.
 - The SOR shall be read along with the relevant clauses of , Vol.II of II which is provided in the tender document.
 - Prices quoted shall be inclusive of all taxes/duties and nothing extra shall be payable by the owner other than statutory variation in GST rate
 - Price bid evaluation will be carried out inclusive of all taxes & duties i.e. inclusive of GST etc.